अनुबंध की सुरक्षा शर्त (अनुलग्नक-डी) / Safety condition of contract (Annexure-D)

SAFETY INSTRUCTION WHILE WORKING AT HEIGHT

1. **FOREWARD**:

Working at heights has the potential to cause serious injuries due to fall for which safeguards like Fencing, use of Toe Boards, safe access to working platforms, Safety Nets, Safety Belts etc are needed. Different types of protective measures need to be adopted suiting the particular task with proper planning and thorough understanding of protective measures and its limitations.

Three metres is the limiting height above which the work should be carried out with utmost care and Work Permit System has to be followed. Moreover, the job should also be carried out under the strict supervision of an experienced person, well conversant with the work and the use of proper PPEs.

Following are some examples of working at height:

- Repair/replacement of Cranes and alignment of their gantries.
- Repairs to exhaust fans /sky jet fans.
- Repairs/ replacement of electrical fittings.
- Cutting of trees and their branches fouling with overhead electrical lines.
- Cutting of wild growth of trees on the walls of buildings.
- Cleaning of high roofs.
- Painting of Walls, Roof Trusses and Chimneys etc.
- Plastering of roof, walls, stairs.
- Casting of R.C.C. roof, beam and columns.
- Demolition of old building and structures.
- Replacement/ repair of fragile Roof Sheets.

Management shall ensure that:

- Appropriate PPE & safety gadgets /equipments required for working at heights is made available and used;
- Workers are trained in the use of safety equipments and are properly supervised;
- Inspection and proper maintenance of safety equipments are undertaken regularly.

2. **NECESSARY DOCUMENTATIONS**:

2.1 Height Pass (permit to work at height)

2.2. **Safety precautions**: Before starting a work at height, all the safety requirement (like use of Safety Belts/Full Body Harness, Life Line protection, Helmets and Safety Nets etc.) shall be decided as per the need of the site by the EIC/ SIC in consultation with safety officer and the contractor where applicable.

2.3 **Safety talk** : Before commencement of work all workers shall be given a safety talk by giving details of work planned.

2.4 **Shut Down of Process, moving equipments etc.**: Before commencement, all moving equipments under the roof sheet where work is to be carried out shall be shut.

2.5. **Warning sign** : Sign boards in Hindi, English and local languages shall be placed at conspicuous places indicating that work is under progress.

3. **REQUIREMENTS FOR WORKERS FOR WORKING AT HEIGHT**:

3.1 **Medical Examination of the worker**: Every worker to be deployed for working height shall be examined for physical and mental fitness and to be certified by a registered medical practitioner at least once is six months. The fitness will include freedom from (a) Epilepsy (b) High BP (c) Obesity (d) Vertigo etc along with general fitness and also a fairly good eyesight.

3.2. **Post training certification (in case of contractor's labourer)** : After successful completion of training and tests, the workers should be issued a height pass which shall be valid for a maximum period of one year. On expiry, it shall be renewed after the worker passes the tests once again.

3.3. Workers should be conversant with the use of Retractable Fall arrester, Life Line, Safe Work Ladder, Duck Ladder, Crawling Board etc. The work of fixing Safety Net be carried out by experienced person and precaution be taken so that the Net is fixed to a structural member sufficiently strong to bear at least one ton load and on sagging under the load of fall the net should not strike a machine structure, part of building or crane etc.

3.4. Each worker should keep one Lifeline always intact and use preferably two Lifelines to avoid any risk to life due to failure of one. Each Life line should be strong enough to bear the shock load due to fall.

3.5. Use of hydraulic / power elevators if used should be known to supervisor & workers.

4. **PPE's AND SAFETY GADGETS**:

4.1. Use of Helmet, proper shoes and other PPEs like Safety Belts, Lifelines with Shock Absorber, Full Body Harness etc. is necessary to prevent a fall and to reduce severity of injuries consequent upon an accident. PPEs and other safety equipment should be provided as per the recommendation of safety officer/ site engineer. Use of Retractable Fall Arrester can eliminate almost all risks and dangers of fall down.

4.2. Examination of PPEs & gadgets e.g. Fall arrestor, Safety belts, Full Body Harness and Safe work ladders etc will be done in presence of Safety Officer at least once in six months.

4.3. Each ladder should have a nylon rope for tying on top and bottom with suitable Self Locking Hooks, Screws, Rings etc.

4.4. If situation permits the use of Fall Arrester and Shock Absorber can be made taking lifeline from a firm structure/ structural member of suitable strength or by tying rope of web of adequate strength with it for this purpose.

4.5. A safety net of suitable strength below the working area should invariably be fixed to cover 2.5 metres all round the work area to arrest a fall. The fixing of such a Net should be carried out by experienced person and precautions be taken to have minimum distance of fall and that the likely sag of safety Net will not cause collision with any plant or machine or a part thereof cranes, structure etc.

5. **EXECUTION OF WORK AT HEIGHT**:

5.1. Safety Net should be used wherever considered necessary and feasible by the EIC/ SIC and safety officer.

5.2. Before starting the day's work, the site should be inspected for ensuring compliance of all safety instruction, regulations and other aspects. After ensuring the compliance, the contractor (when engaged), the EIC/ SIC and the safety officer will sign the relevant documents before giving clearance for starting the work. In the event of discontinuation of work and before restarting, the site inspection shall be redone on the same lines.

5.3. Use of anchor plates to fix the lifeline etc should be done wherever necessary/ feasible.

5.4. In case the site condition demands, a Safety Net may be fixed firmly on the fragile roof with the help of J bolts and this may be used for taking a Life Line. Proper training for the above should be imparted to workers working on fragile roof and in any case fragile roof should not be taken granted as safe. During the rescue operation Safety belt should be avoided as far as possible and full body harness should be used.

5.5. In any case, contractors should not be allowed to execute the work by engaging market labourers while there is requirement of working at height in any of the contract agreement related to Civil Works.

5.6. Insurance of all the workmen working at height must be submitted before commencing the work.

5.7. **Risk Assessment:** Conduct a detailed and thorough risk assessment prior to starting execution of work at height more than 3meters viz. Fragile sheet (roof)repairing/replacing work. This assessment should include an analysis of load bearing capacity of old fragile sheet and proper positioning of experienced personnel / workers at height equipped with PPEs. Unauthorized approach by any person to the work place at height must be restricted.

5.8. **Supervision and Coordination:**

a) Appoint a dedicated site in-charge from the section where the work is being executed to Coordinate with safety section and will ensure strict adherence to safety procedures.

b) It is to be also ensured that contractor should engaged supervisor and workmen as different persons and supervisor must be available at the site continuously for proper supervision and guidance to the workmen.

c) Supervisor must give the training /safety talk to the workmen those are engaged in working at height.

5.9. **Communication Protocols:** Establish clear and standardized communication signals between workmen working at height and supervisor to avoid confusion during execution of the work.

5.10. **Demarcation of Danger Zones:** Clearly demarcate danger zones around / below the working at height area to restrict entry by unauthorized person.

6. **LADDER**:

The use of ladders is so common that we are apt to take them for granted, however they are involved in many accidents in industry which could easily be prevented by observing four simple rules.

- Don't use ladders where the job calls for something bigger and safer.
- Use the right kind of ladder for the job.
- Use only a ladder in a good condition.
- Use ladders safely
- Don't use a ladder too long or too short for the job. For the scaffolding and ladders the following maximum lengths be permitted.

  For a single ladder : 30ft.
  For a step ladder : 18ft.
  For a trestle ladder : 16ft.
- Don't use two ladders sliced together (unless the resulting ladder is just as strong as a single or extension ladder would be).
- Don't use light ladders for a heavy construction job.

- Don't use metal ladders near electrical circuits or power lines to the excellent performance & if unavoidable their insulating rubber shoes should be checked before use.
- To set up a ladder safely, the base should be one fourth the ladder length from the vertical plane of the top support (1:4). Tie-off should be adequate to prevent any tipping of the ladder if the climber leans to the side.
- Don't use a ladder if the side rails are broken or cracked, or if a rung or tread is missing, broken, weakened or in any way defective.
- Ladders should never be painted because paint tends to hide cracks. They should be kept free of dirt, splashing of paint and moisture. If any preservative is needed it should be a clear varnish or some other transparent coating.
- The horizontal distance from the wall to the foot of the ladder should be about a quarter of the ladder's length.
- Don't place the ladder on an uneven footing or on loose objects. Where possible, fix it so that the top and bottom ends cannot move;
- Don't place the ladder in front of a door unless the door is fastened open or locked or guarded.
- Don't work above the second top rung on a straight ladder. Hold on with one hand and don't push, pull or over-reach. Don't straddle the space between the ladder and another object.
- When going up or coming down have both hands free and face the ladder.
- Ladders are built to hold only one person at a time. Remember this when using ladders.
- When leaning a ladder against a window frame fix a board to the top so that the weight is spread safely over the window frame.
- Ladders should be tied off or stabilized at the earliest opportunity in such a way that they cannot tip to the side or slide in any way.
- The three-point control while climbing helps ensure that a worker's centre of gravity is within the side rails and capacity exists for holding the ladder if a fall occurs. When ladders are provided with slip -resistance, it should be remembered that the end of the rung is probably the best place to hold a ladder, if the ladder rung is rough at these points, gloves are required, but the user may still prefer to hold the side rail which does not usually provide a graspable element.
- The portable ladder is preferred to be sloped at the appropriate angle for stability and this slope provides a measure of fall protection when a fall occurs.
- Since metal ladders conduct electricity do not use them around energized electrical circuits equipment, or in places where they may come in contact with electrical circuits. Warn workers using metal ladders about these dangers. Plastic or glass-fiber ladders, as well as wood ladders, should be considered for use near electrical hazards. Many construction projects forbid metal ladders.

7. SPECIAL SAFETY PRECAUTIONS FOR REPAIR OF O.H. CRANES:

- A safe system of work should be ensured before any maintenance repair or adjustment is required to carry out work on a crane, a permit to work system may be necessary to achieve safe system of work. To achieve the above following precautions should be ensured.
- Electrical power to crane should be disconnected before undertaking any repair etc.
- After repair it should be ensured that all tools, oil, grease etc have been removed from work place/site. And also guard has been replaced.

- Should be ensured that all limit switches are working to avoid overrun of the crane.
- Edges should be provided at wheels to avoid undesirable movement of crane.
- Parallelism of the gantry should be checked at specified periodicity.
- After every major repair crane should be subjected to load test.
- For climbing on cranes ladders should be provided with safety cage guard.
- During repair warning note should be provided both at the switching box of crane and work site.

8. SPECIAL PRECAUTIONS:

- During climbing on roof or on electric pole using ladder or otherwise precautions should be taken to use two self locking hooks with lifelines and as climbing these hooks should be alternatively attached and detached with the cross bars/ foot bars to prevent any eventual fall due to slippage etc leaving no room for a fall. After reaching the roof the top end of the ladder should be tied to the pole/ fixed structure on top of the roof and work should be started thereafter.
- A safe way of climbing on a roof is to use a hydraulic / electric lift platform which is commercially available for climbing up to 7 metres height and to carry up to 250 kgs. load. These platforms are provided with railings all round which may be used for fixing lifelines with detachable hooks with shock absorbers or else a retractable fall arrester.
- The workers working at height should be cautioned not to allow leaving of loose items like broken sheets over the roof after completion of work which can be flown off during heavy winds. While climbing they should take their tools in a tool box firmly fixed to the safety belt and should ensure that nothing is left loose on the roof at the close of work.
- In case of welding or drilling the use of approved quality of cable should be done to lay the electrical lines for connection.
- They broken sheets and new sheets should be taken up the roof or lowered from it in properly tied bunches with rope and not many sheets should be taken at a time. The hydraulic platforms and ladders should never be overloaded.
- A safety Net be spread and fixed over the roof with J-bolts for safe movement of workers.

DO's AND DONT's WHILE WORKING AT HEIGHT

Do's

1. While going to work at height for more than 3 metres, wear Safety Helmet & Antiskid Shoes.
2. Use Crawling Boards or Roof Ladders while working on the roof of the building.
3. Safety Belt should be worn by the individual while working at a height more than 3 metres. Lifeline should be tightened to a fixed structure.
4. Safety Net should be placed below the place of work at height.
5. Safety items like Safety Belt, Safety Net, Safety Helmet and Lifeline should be inspected periodically by the staff or Site In charge/ EIC.
6. Ladders should be tightened to a fixed structure and have Antiskid Shoes.
7. Responsible staff should be present continuously at the work spot.
8. Scaffolds should be of good construction, sound material and adequate strength.
9. Only trained and experienced workmen should be allowed to work at height.
10. Ladder should always be held by helper.

Don't's

1. Do not work without Work Permit and follow the safety instructions enumerated therein.
2. Do not leave the tools on the roof top and other places where they are liable to fall and cause injuries.
3. Do not use loose clothing while at work.
4. Do not smoke while working at height.
5. Do not forget to position First- Aid Equipment in the work place.
6. Do not allow individuals having heart problems, giddiness, vertigo, epilepsy, high BP, to work at height.
7. Work on the roof of the building shall not be carried out in rainy season, windy condition and hot summer.
8. Do not allow anyone to work in the Shop floor area below the roof work so that accidents can be avoided due to hit by fallen material from height.
9. Do not bend/ stretch the body outside the ladder/ platform.
10. Do not place the ladder where they can be struck by doors, vehicles.
11. Ladder should not have slope more than 4 vertical and 1 horizontal.

Standard Work Permit Format

Part – I

(To be issued Before Commencement of the Work)

Ordnance Factory/Unit Name :.....

Work Permit No.: ..... Date &Time of issue:.....

Permit Duration: from..... To.....

1. Details of the Work:

   .....

2. Exact location of Work Site: .....
3. Name of Contractor/Firm:
4. Name & designation and signature of Site In Charge

   .....

5. Name, designation & signature of Work site Nominated person:

   .....

6. Name & signature of Contractor' s Supervisor/Supervisors:

   .....

7. Assessment of general before requirements before issue of Permit

Sl.No.	Requirement	Condition	Remarks of Safety Officer where not specified
1	Electrical shut down	Yes/NO	Name Designation and signature of Concerned EM Staff
2	Ladder	Yes/NO	
3	Full body harness double lanyard as per IS 1531	Yes/NO	
4	Safety Helmet as per 152925	Yes/NO	
5	Hand gloves	Yes/NO	
6	Safety Shoes	Yes/NO	
7	Safety Net, as per IS 11057	Yes/NO	
8	Safe Walk/crawling ladder	Yes/NO	
9	Oxygen Cylinder and other emergency arrangements	Yes/NO	Please specify
10	Safe Working Instructions are known to contractor's supervisor	Yes/NO	
11	Medical Certificate of workers	Yes/NO	
12	Others	Yes/NO	

Workers authorized to work requiring permit:

Sl.No.	Name of workers	Age in completed years	Medical Certificate date	Signature

This work permit will be considered valid only if the associated part II and III are adhered to

Permit Raised By	Site Clearance given By	Permit issued by	Permit received by
JWM/EW(CC)/CE/EM/MM	HOS Concerned Section	Safety officer(Name & Designation)	Contractor(Name &Seal)

Part – II

(To be maintained on daily basis before start of work during the permit period)

Work Permit No.: ..... Permit issue date :----------
Date of Work:----------

A Daily Safety/ Safe Practice Checklist:

Sl.No.	Items Requirement	Yes /NO	Remarks of Site in charge if any
1	Site is cleared for working with compliance of all safety instructions. If roof working is involved then there is no rain, thundershowers or excessive heat.	Yes/NO	
2	Electrical shut down required	Yes/NO	
3	Ladder is sound and being used safely (single ladder up to 30 feet)	Yes/NO	
4	Body harness double lanyard is being and tied properly	Yes/NO	
5	Safety Helmet is being used	Yes/NO	
6	Safety Shoes are being used	Yes/NO	
7	Hand gloves are being used	Yes/NO	
8	Safety net is being used and fixed properly	Yes/NO	
9	Safe walk ladder is placed and fixed properly	Yes/NO	
10	Contractor's supervisor is available and well aware about the safety instructions (AWEIL HQ instructions for working at height)	Yes/NO	
11	Safe Working instructions are given to the workmen in the local language by Contractor's supervisor before commencement of work	Yes/NO	

B. Workers actually engaged from the list authorized in part - I :

Sl.No.	Name of workers	Age in completed years	Medical Certificate date	Insurance Certificate No.	Signature
1					
2					

Contractor's Supervisor has to ensure that the contractor's men are always wearing safety gadgets and safe practices are followed.

Contractor Supervisor	Section Nominated Staff	Site in Charge
(Name & Seal)	(Name & Designation)	(Name & Designation)

Part – III

(Monitoring of work during permit duration)

Work Permit No.: ..... Permit issue date :----------

Surprise visit details (if any conducted by the Safety officer (SO) and Chief Safety Officer (CSO):

Sl.No.	Visit date & time	Visit conducted by the SO/CSO	Action taken details (in case of deviations if any)
1			
2			

Work Permit Closure Date & time: ----------

Safety Officer
(Name & Designation)

Chief Safety Officer
(Name & Designation)